2. Plans and detailed estimate and conditions may be seen in the Municipal Executive Engineer's office during office hours.

3. A statement in the form given below showing the rates at which the different items specified will be executed should accompany the tender.

4. Tenders must be accompanied by a deposit of Rs. 200 (in cash or currency notes) as earnest money, and be superscribed " Tender for constructing a Sheep Slaughter-house in Bangalore City."

5. The acceptance of any tender rests with the President, City Municipal Commission, Bangalore, who does not bind himself to accept the lowest or any tender or assign reasons for the rejection of any tender.

6. The name of the successful tenderer will be posted on the notice board in the Municipal office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. The successful tenderer will be required to execute a bond within a week after the acceptance of his tender. In default, the tenderer will forfeit his earnest money and his tender will be considered cancelled.

8. The earnest money of the rejected tenderers will be returned on the acceptance of one of the tenders.

Items of work.	Per.	Quantity.
Earthwork excavation	C. yd.	318
Concrete work	C. ft.	1,952
Burnt stone in clay	Do	10,356
Burnt brick in clay	Do	7,088
Arch work	Do	42
Burnt stone slabs, ordinary	S. ft.	790
Cement plastering	Sq.	25·63
Chunam plastering	Do	80·90
White-washing	Do	32·32
Colour-washing	Do	50·04
Pointing with chunam	Do	16·98
Teakwood work, rought and put up including wood oiling	C. ft.	443·37
Eave board	R. ft.	776
Roofing with 1st class Mangalore tiles, teak reapers including ridge tiles, &c., complete	Sq.	38·20
Teakwood door for hanging-room with hinges, bolts and painting, &c. ..	S. ft.	72
Teakwood windows with iron bars including painting, complete ...	Do	311
Glazed ventilators with iron bars including rivetting and painting, &c. ...	Do	81
Circular glazed ventilators with iron bars & complete	No.	2
Corrugated iron sheet with holes and nuts including fitting charges ...	Sq.	26·37
V-shaped drain including cement plastering	R. ft.	246
Flooring with roughly dressed slabs including concrete and cement pointing complete	Sq.	34·83
Flooring 6″ concrete including cement plastering	Do	4·31
Iron bars for hanging-room (1 diameter)	lbs.	200
Iron hooks for Slaughter shed	No.	148
Cutting groves for pillars	No.	14
Zinc sheet gutter	R. ft.	20
Zinc sheet gates with bolts and nuts, &c.	No.	20
Forming roads	Lump	sum.
Earth-filling	C. yds.	431

N. B.—The quantities are not guaranteed.

H. H. SPARKES, *President.*

GOVERNMENT CENTRAL BOOK DEPOT, BANGALORE.

Notice dated 7th October 1903.

It is hereby notified for information that copies of outline maps of Europe, World, Asia, England & Wales, Scotland and India, (published by Messrs. Longmans, Green & Co.), are available for sale.

The price of a copy of each is 4 pies.

S. ABDUL HAI, *Curator.*